



ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಯಲಹಂಕ ವಲಯ

ಬೆಂಗಳೂರು-92.



ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ ಕಛೇರಿ
ಬೃ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು-92.

ದೂರವಾಣಿ: 23636671

ಸಂಖ್ಯೆ: ಬೃ.ಬೆ.ಮ.ಪಾ/ಬ್ಯಾ.ವಿ/ಕಾ.ಅ/ F10/2015-16
16942

ದಿನಾಂಕ: 16/04/2015

ರವರಿಗೆ,

N. Keerthi
#66, Anandappa building
Hospital road, Yelahanka
Bangalore-64.

ಮಾನ್ಯರೇ,

ವಿಷಯ:- Road Development and asphaltting works at
Singapoore layout cross roads in ward no. 11.
ಕಾಮಗಾರಿಗೆ ದರಸಂದಾನಕ್ಕೆ ಆಹ್ವಾನಿಸುವ ಬಗ್ಗೆ.

ಗುತ್ತಿಗೆದಾರರಾದ ತಾವು ಇ-ಪ್ರಕ್ಯೂರ್‌ಮೆಂಟ್ ಟೆಂಡರ್ ಸಂಖ್ಯೆ: 10/14-15, ದಿ:

21.02.2015ರ ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ: 16942 ಭಾಗವಹಿಸಿದ್ದು, ನೀವು ಏಕೈಕ
ಗುತ್ತಿಗೆದಾರರಾಗಿರುತ್ತೀರಿ. ಆದ್ದರಿಂದ ಸದರಿ ಕಾಮಗಾರಿಯನ್ನು ನಿರ್ವಹಿಸಲು ತಮ್ಮನ್ನು
ದರಸಂದಾನಕ್ಕೆ ಆಹ್ವಾನಿಸುತ್ತಾ, ಈ ಪತ್ರ ತಲುಪಿದ 3 ದಿನಗಳೊಳಗಾಗಿ ದರಸಂದಾನ ದರಗಳನ್ನು
ಸಲ್ಲಿಸಲು ಸೂಚಿಸಿದೆ. ಇಲ್ಲವಾದಲ್ಲಿ ನಿಮ್ಮ ಟೆಂಡರ್‌ನ್ನು ರದ್ದುಪಡಿಸಿ ಮರುಟೆಂಡರ್
ಕರೆಯಲಾಗುವುದು ಈ ಬಗ್ಗೆ ಇನ್ನು ಮುಂದೆ ಯಾವುದೇ ತಿಳುವಳಿಕೆ ಪತ್ರಗಳನ್ನು
ನೀಡಲಾಗುವುದಿಲ್ಲ.

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92.

ರವರಿಗೆ,

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92.

ಮಾನ್ಯರೇ,

ವಿಷಯ:- ಧರಸಂದಾನ ನಡೆಸುವ ಬಗ್ಗೆ.

ಉಲ್ಲೇಖ:- ತಮ್ಮ ಪತ್ರದ ದಿನಾಂಕ: 16/04/2015

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ಟೆಂಡರ್ 10/14-15 ದಿನಾಂಕ: 21.02.2015ರ
ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ: 16942 ಕ್ಕೆ ನನ್ನ ಧರಗಳನ್ನು ನಮೂದಿಸಿ ನಿಯಮಾನುಸಾರ ಟೆಂಡರ್
ಸಲ್ಲಿಸಿರುತ್ತೇನೆ. ನಿಮ್ಮ ಕಛೇರಿ ಪತ್ರದಂತೆ ದರ ಸಂಧಾನಕ್ಕೆ ಒಪ್ಪಿದ್ದು, ಟೆಂಡರ್‌ನಲ್ಲಿ ನಮೂದಿಸಿದ್ದ
ದರಗಳಿಗಿಂತ -0.25% ಕಡಿಮೆ ದರಗಳಿಗೆ ಕಾರ್ಯ ನಿರ್ವಹಿಸಲು ಒಪ್ಪಿಸುತ್ತೇನೆ.

DM
16/04/2015

N. K. K. K.
ತಮ್ಮ ವಿಶ್ವಾಸಿ

BRIIHT BENGALOORE MAHANARA PALIKE, YELAHANKA ZONE

BYATARA YANAPURA DIVISION

SCHEDULE-B (As Per Negotiated)

BBMP/2014-15/RD/WORK INDENT16942

Road Development and asphaltting works at Singapore layout cross roads in ward no. 11.

Sl. No.	Description	Item Code	Unit	Qty	Sanctioned Estimate		Rates Quoted Before Negotiation N KEERTHI		Rates Quoted After Negotiation N KEERTHI	
					Rate	Amount	Rate	Amount	Rate	Amount
1	Earth work excavation by manual means in ordinary soil involving 1		Cum	406.8	75.6	30754.08	80.0	32544.00	75.41	30677.19
2	Earth work excavation by manual means in hard soil involving an 2		Cum	423.75	105.84	44849.7	110.0	46612.50	105.58	44737.58
3	Removing B.S Slab of Drain and stacking etc complete as per sp 3		Sqm	756	58.32	44089.92	70.0	52920.00	58.17	43979.70
4	Refixing stone slabs of drains and pointing in C.M (1:3) etc comp 4		Sqm	756	75.6	57153.6	80.0	60480.00	75.41	57010.72
5	Providing, laying, spreading and compacting graded stone aggregate 5		Cum	508.5	1438.6	731507.76	1450.0	737325.00	1434.96	729678.99
6	Cleaning the existing WBM road surface including removing of bit 6		Sqm	2825	12.2	34465	15.0	42375.00	12.17	34378.84
7	Providing and applying primer coat for surfaces of medium porous 7		Sqm	2825	74.52	210519	85.0	240125.00	74.33	209992.70
8	Providing and laying semi dense bituminous concrete using crushed 8		Cum	70.63	11070	781874.1	11500.0	812245.00	11042.33	779919.41
9	Lead for Disposal of Debris shall be payable at carriage rates by 9		Cum	581.39	73.57	42772.862	80.0	46511.20	73.39	42665.93
	Total					1977986.02		2071137.70		1973041.06
							N KEERTHI		N KEERTHI	
							2071137.70 -1977986.02		1973041.06 -1977986.02	
							93151.68 4.71%		-4944.97 -0.25%	
							Over Sanctioned Rates		1977986.02	

The Lowest Rates Quoted by N KEERTHI, Contractor is 0.25% Below the Sanctioned Estimate rates is recommended for kind Approval.

Aug 16/04.

Assistant Engineer
Byatarayanapura Division

Executive Engineer
Byatarayanapura Division

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16942

NEGOTIATION SCHEDULE - B

EE/BTP/BBMP/E-PMT/11/2014-15, Date: 25.03.2015

Road Development and asphaltting works at Singapoore layout cross roads in ward no. 11.

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of N KEERTHI	
				In Figures	In Words
1	406.8	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	75.41	
2	423.75	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	105.58	
3	756	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	58.17.	
4	756	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	75.41	
5	508.5	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1434.96	
6	2825	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	12.17.	
7	2825	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	74.33	



Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of N KEERTHI	
				In Figures	In Words
8	70.63	Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (25-30mm) with 5% CRMB-55 grade, etc complete as per specifications and directions of engineer in charge of the work	Cum	11042.33	
9	581.39	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. etc complete as per specifications and directions of engineer in charge of the work	Cum	73.39.	

Signature of the Contractor *N. Keerthi*

[Signature]
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92